108982

# Plate Heat Exchanger



**Technical Specification** 

Customer : E. I. DuPont

Model

: TS6-MFG

Project: : Danisco PF HX Package 9-17-09
Item : F900 FT TW HX-TS6MFG

Item

: E900 ET TW HX-TS6MFG

Date: 11/14/2009

Fluid Density Specific heat capacity Thermal conductivity Viscosity inlet Viscosity outlet	lb/ft³ Btu/lb,°F Btu/ft,h,°F cP cP	Hot Side Steam 0.1298 0.55 0.0163 0.0139 0.0139	Cold side Water 62.45 1.00 0.338 1.52 1.27
Batch mass Start temperature End temperature Batch time Volume flow rate Inlet temperature Outlet temperature Pressure drop	Ib °F °F min GPM °F °F	6618 41.0 104.0 60.00 505.8 290.7 290.7 0.0564	41.0 52.0 7.62
Heat Exchanged L.M.T.D. O.H.T.C service Heat transfer area Relative directions of fluids Number of plates Effective Plates Number of passes Extension capacity	kBtu/h °F Btu/ft²,h,°F ft²	482.8 244.1 268.1 7.4 Countercurrent 10 8 1	1
Plate material Sealing material ON		ALLOY 316 EPDMP CLIP-ON	EPDMP CLIP-
Connection material Connection diameter Nozzle orientation	in	Stainless steel 3 S4 -> S3	Stainless steel 3 S1 <- S2
Pressure vessel code Flange rating Design pressure Test pressure Design temperature	psi psi °F	ASME ASME 150 150.0 195.0 347.0	150.0 195.0 347.0
Overall length x width x height Liquid volume Net weight, empty / operating	in ft³ lb	21 x 16 x 28 0.1 275 / 280	0.1

Performance is conditioned on the accuracy of customers data and customers ability to supply equipment

Data, specifications, and other kind of information of technological nature set out in this documentand submitted by Alfa Laval to you (Proprietary Information) are intellectualproprietary rights of Alfa Laval. The Proprietary Information shall remain the exclusive property of Alfa Lavaland shall only be used for the purpose of evaluating Alfa Lavals quotation. The Proprietary Information may not, without the written consent of Alfa Laval, be used or copied, reproduced, transmitted or communicated or disclosed in any other way to a third party.

#### **Equipment Data Sheet**

### ET Tempered Water Heat Exchanger Sheet 1 of 3



Date/ Author/ Revision September 3, 2009 DCF/ALS Rev. 0 **Equipment Identification** Plate & Frame Heat Exchanger Equipment Type: **Equipment Name:** ET Tempered Water Heat Exhanger Tag: E900 PID: P200 System Heat-up Duty: Raise the temperature of cooling tower water make-up and the system metal mass Service Description: from ambient to the tempered water circulation temperature required for process heating. Process Heating Duty: Maintain the operating temperature of the tempered water circulated through the process tank jacket as required for process heating. **Batch Heating** Application Type: Use, hr/day / days/week 8/5 Manufacturer, Model: By Supplier Attachments The following files are part of this Equipment Data Sheet and are to be included as attachments: E900 ET Tempered Water Heat Exchanger VD DCF R0.pdf Duty Water Flow Rate, kg/hr (Cold Side) 19,870 Cold Side In Hot Side 2.0 Cold Side Out 1.3 3.0 Operating Pressure, barg System Heat-up Initial System Metal Temp., C Initial System Water Temp., C Final System Temperature, deg C 80 TW System Liquid Inventory, kg 628 TW Specific Heat, kcal/kg K 1.00 TW Liquid Sensible Duty, kcal 32,700 2,425 System Metal Mass, kg Metal Specific Heat, kcal/kg K 0.12 Metal Sensible Duty, kcal 18,900 Total Heat-up Heat Load, kcal 51,600 Heat-up Time, min 30 Average Duty, kcal/hr 103,200 Average duty overall system heat-up step. 200 Average Steam Rate, kg/hr This maximum duty case accounts for higher heat Maximum (Design) Duty, kcal/hr 127,400 transfer rate required at start of the system heat-up step Maximum Steam Rate, kg/hr 250 71,300 Minimum Duty, kcal/hr This minimum duty case represents maximum turndown requirement which will occur at the end of 140 Minimum Steam Rate, kg/hr the system heat-up step Process Heating Process Heating Time, min 60 Initial Process Temperature, C 5 Final Process Temperature, C 40 Process Liquid Mass, kg 2,995 105,100 Total Heat-up Heat Load, kcal Average Duty, kcal/hr 105,100 Average duty overall process heating step duration. Average Steam Rate, kg/hr 210 Cold Side Water Temp. @Avg. C Inlet 75 Outlet 80 Maximum (Design) Duty, kcal/hr 147,700 Maximum duty is the higher heat transfer rate required Maximum Steam Rate, kg/hr 290 at start of the process heating step. Cold Side Water Temp. @Max. C Inlet 73 Outlet 80 Minimum duty is the lower heat transfer rate required Minimum Duty, kcal/hr 81,500 at end of the process heating step. Minimum Steam Rate, kg/hr 160 Inlet 76 Outlet 80 Cold Side Water Temp. @Min. C

# **Equipment Data Sheet**

## ET Tempered Water Heat Exchanger Sheet 2 of 3



Equipment Identification								
Equipment Type:	Plate & Frame He	at Excl	nanger					
Equipment Name:	ET Tempered Wa	ter Hea	t Exhanger					
Tag:	E900							
PID:	P200							
Fluid Properties	Cold Side			Hot Side				
Fluid	Tempered Water				Steam			
Temperature, deg C	28.0		80	0.0	143.7 @Sat 3.0 bar			
Density, g/ml	0.996		***************************************	72	0.	00214		
Specific Heat, kcal/kg K	0.993			002		0.456		
Viscosity, cp	0.833		***************************************	354		.0135		
Thermal Conductivity, W/m K	0.580			000		.0292		
Latent Heat, kcal/kg				-		509		
Molecular Weight	18.015		18	015	1	8.015		
Design Data	10.010	Co	ld Side	010		Hot S	ide	
Max Allowable Pressure Drop, bar		0.70		0.7				
Fouling Factor, W/m2 C	<b></b>				By Supplier			
Design Pressure, barg	By Supplier				10			
Test Pressure, barg	<del> </del>		14.9		14.9			
Design Temperature, deg C			175			17:	***************************************	
Heat Transfer Area, m2			170	By Su	I Innlier	173	,	
Overall Heat Transfer Coefficient	·····							
	By Supplier							
Number of Plates	By Supplier							
Overdesign Factor, %	10% Minimum By Supplier							
Weight - Empty, kg	·····			15% M				
Additional Plate Capability, %		True = -17		13% IVI	mmum			
Materials of Construction				101 204 2041	Otalalaaa (	Dia al		
Plates	AISI 304 or 304L Stainless Steel							
Frame	Carbon Steel - Note 1 Stainless Steel							
Guide Bars				***************************************				
Carrying Bars	Stainless Steel							
End Plates				Carbon Ste	*****************************	. N. 1 - 0		
Connections			************************************	304 or 304L Sta	**************************			
Shroud	***************************************		<i>F</i>	ISI 304 or 304l		Steel		
Plate Gaskets	EPDM - Note 3							
Nuts/Bolts				304	ISS			
Notes			= = = = = = = = = = = = = = = = = = =					
Carbon steel components shall be		olier's S	tandard coatin	g system.				
2. Connections shall be 150# Flang								
<ol><li>Vendor shall confirm that EPDM</li></ol>			esign temperati	ıre.	1 11			
Exchanger Weight	l k	g		W 9= 11 = 1	lb	0 11 1		
Empty Weight			Supplier to			Supplier to		
Weight Full of Water			Complete			Complete		
Maximum Operational Weight					_			
nsulation								
Function	Energy Conservati							
nsulation Material with Cover	Mineral Wool with & Bands		_		& Installed			
nsulation Supports & Tabs	Approved Vendor Standard			Supplier t	Supplier to Submit for Approval			
	mm		inch					
nsulation Thickness	50.8		2.0					
Allowance for Insulation (Use for	]					100		
						1		
Allowance for Insulation (Use for								

### **Equipment Data Sheet**

### ET Tempered Water Heat Exchanger Sheet 3 of 3



Date/ Author/ Revision DCF/ALS September 3, 2009 Rev. 0 Equipment Identification Equipment Type: Plate & Frame Heat Exchanger Equipment Name: ET Tempered Water Heat Exhanger Tag: E900 P200 SYSTEM SKETCH Process Vessel Cooling Tower
Water Supply Jacket 3.5 barg Steam 3.5 barg Cnds Т Tempered Water Heater Tempered Water Pump Cooling Tower Water Return